



VERSIWELD TPO

G U I D E - S P E C

VersiWeld® TPO Mechanically Attached Roofing System

January 2012

This **GUIDE-SPEC** is a brief outline of Versico's VersiWeld Mechanically Attached Roofing System requirements and is intended for use as a submittal with a bid package. Specifiers and the Versico Authorized Roofing Contractor must comply with the applicable sections of Versico's Technical Manual prior to design or bid.

PART I GENERAL

1.01 DESCRIPTION

The VersiWeld Mechanically Attached Roofing System incorporates 12', 10' or 8' wide, white, gray or tan 45, 60 or 80-mil thick scrim-reinforced VersiWeld Thermoplastic Polyolefin (TPO) membrane. Insulation is mechanically fastened to an acceptable roof deck. VersiWeld perimeter sheets (6' or 4' wide respectively) are installed along the building edges and field membrane sheets are mechanically fastened to the roof deck with the appropriate Versico Fasteners and Fastening Plates. Adjoining sheets of VersiWeld membrane are overlapped and joined together with a minimum 1-1/2" wide hot air weld. Refer to the Thermoplastic Specification for the required number of perimeter membrane sheets and the required fastener spacing.

1.02 QUALITY ASSURANCE

- A. This roofing system must be installed by a Versico Authorized Roofing Contractor in compliance with shop drawings as approved by Versico.
- B. Upon request, an inspection shall be conducted by a Field Service Representative of Versico to ascertain that the membrane roofing system has been installed according to Versico's published specifications and details applicable at the time of bid. This inspection is to determine whether a warranty shall be issued. It is not intended as a final inspection for the benefit of the owner.
- C. For specific code approvals achieved with this system, refer to Versico's VersiWeld Code Approval Guide, FM Approvals or UL Fire Resistance Directory for Roofing Materials and System.

1.03 SUBMITTALS

- A. To ensure compliance with Versico's warranty requirements, the following projects should be forwarded to Versico for review prior to installation, preferably prior to bid.
 - 1. Air pressurized buildings, canopies, and buildings with large openings, cold storage buildings or freezer facilities, adhered roofing system projects over 100' in height or projects where the membrane is expected to come in direct contact with petroleum-based products, waste products (i.e., grease, oil, animal fats, etc) and other chemicals.
- B. Shop drawings must be submitted to Versico by the Versico Authorized Roofing Contractor along with a completely executed Copy-A – Job Approval Request for approval. Approved shop drawings are required for inspection of the roof and on projects where on-site technical assistance is requested.

1.04 GENERAL DESIGN CONSIDERATIONS

- A. It is the responsibility of the building owner or his/her designated representative to verify structural load limitation. In addition, a core cut may be taken to verify weight of existing components when the roofing system is to be specified on an existing facility.
- B. On new construction projects, especially in cold climate regions, moisture generated due to the construction process could adversely impact various components within the roofing assembly if not addressed. Refer to Spec Supplement G-01-11 "Construction Generated Moisture" included in the Versico Technical Manual.
- C. On structural concrete decks, when a vapor retarder is not used, gaps in the deck along the perimeter and around penetrations must be sealed along with vertical joints between tilt-up panels, if present, to prevent infiltration of hot humid air and possible moisture contamination resulting from condensation. This is specifically important when adhesive is used to attach the roof insulation.

CAUTION: If left unaddressed, collected moisture could weaken insulation boards and facers resulting in a blow-off or increase the probability of mold growth.



D. Vapor Retarders

1. Versico does not require a vapor retarder for the protection of the membrane; however, it should be considered by the specifier for the protection of the roofing assembly (i.e. primarily insulation, underlayment and adhesives). The following criteria should be considered by the specifier:
 - a. Use of a vapor retarder to protect insulation and reduce moisture accumulation within an insulated roofing assembly, should be investigated by the specifier.
 - b. In the generally temperate climate of the United States, during the winter months, water vapor flows upward from a heated, more humid **interior toward** a colder, drier exterior. Vapor retarders are more commonly required in northern climates than in southern regions, where downward vapor pressure may be expected and the roofing membrane itself becomes the vapor retarder.

1.05 WARRANTY

Table I Mechanically Attached Membrane Systems Warranty Options (6)

Years	Thermoplastic Membranes (VersiWeld TPO)				
	55, 72, 80 or 90 mph	100 mph	110 to 120 mph	Minimum Membrane Thickness (5)	Additional Puncture Coverage (2)
	Mech. Fastened	Mech. Fastened	Mech. Fastened		
5,10, or 15 year	√	N/A(1)	N/A	VersiWeld 45-mil	Not Available - 80-mil Membrane Required
20 year	√	N/A	N/A	VersiWeld 60-mil (3)	Not Available - 80-mil Membrane Required
25 year (6)	√	N/A	N/A	VersiWeld 80-mil (4)	Available
30 year (6)	√	N/A	N/A	VersiWeld 80-mil (4)	N/A

Notes: N/A = Not Acceptable √= Acceptable

- (1) Contact Versico for specific requirements.
- (2) Limits of Hail/Puncture Coverage to be defined by other Tables.
- (3) Spectro-Weld TPO 60-mil membranes may be used in lieu of VersiWeld 60-mil membrane.
- (4) Spectro-Weld TPO 80-mil membrane can be used in lieu of VersiWeld 80-mil membrane.
- (5) All “T-Joints” must be overlaid with appropriate flashing material when using 60 or 80-mil membrane.
- (6) Enhancements may be required for certain flashing details. Published details must be referenced for applicable requirements.

1.06 PRODUCT DELIVERY, STORAGE AND HANDLING

- A. Deliver materials to the job site in the original, unopened containers labeled with the manufacturer's name, brand name and installation instructions.
- B. Store VersiWeld membrane in the original undisturbed plastic wrap.
- C. Job site storage temperatures in excess of 90° F may affect shelf life of curable materials (i.e., adhesives and sealants).
- D. When liquid adhesives and sealants are exposed to lower temperatures, restore to a minimum of 60° Fahrenheit before use.
- E. Do not store adhesive containers with opened lids due to the loss of solvent, which will occur from flash off.

1.07 JOB CONDITIONS

- A. Refer to Versico Technical Manual for applicable project specific Job Conditions.

PART II PRODUCTS

2.01 GENERAL

The components of this roofing system are to be products of Versico or accepted by Versico as compatible. The installation, performance or integrity of products by others, **when selected by the specifier and accepted by Versico**, is not the responsibility of Versico and is expressly disclaimed by the Versico Warranty.

2.02 MEMBRANE

VersiWeld white, gray or tan 45, 60 or 80-mil thick reinforced Thermoplastic Polyolefin (TPO) membrane is used for this system. Field membrane sheets are 12', 10' or 8' wide by 100' long based on project conditions. Perimeter sheets are 6' wide (used with 12' or 10' field sheets), or 4' wide (used with 8' field sheets).

2.03 RELATED MATERIALS

VersiWeld Non-Reinforced or Reinforced Flashing, Bonding Adhesive, Cut Edge Sealant, Water Cut-Off Mastic, Weathered Membrane Cleaner, Molded Pocket Sealant, Heat Weldable Walkway Pads, Pre-Molded Inside/Outside Corners, Pipe Flashings, Curb Wraps and Sealant Pockets.

PART III EXECUTION

3.01 GENERAL

- A. When feasible, begin the application at the highest point of the highest roof level and work to the lowest point to prevent moisture infiltration and to minimize construction traffic on completed sections. This will include completion of all flashings, terminations and daily seals.

3.02 ROOF DECK CRITERIA

- A. Proper substrate shall be provided by the building owner. The structure shall be sufficient to withstand normal construction loads and live loads.
- B. Defects in the roof deck must be reported and documented to the specifier, general contractor and building owner for assessment. The Versico Authorized Contractor shall not proceed with installation unless defects are corrected.
- C. Refer to Versico Technical Manual for acceptable decks and the applicable Versico Fasteners (when mechanical attachment of insulation is specified).

3.03 SUBSTRATE PREPARATION

- A. On retrofit-recover projects, cut and remove wet insulation, as identified by specifier, and fill all voids with new insulation so it is relatively flush with existing surface.
- B. For all projects, substrate must be even without noticeable high spots or depressions, and must be free of accumulated water, ice or snow.
- C. Clear the substrate of debris and foreign material. Fresh bitumen based roof cement must be removed or concealed.

3.04 INSTALLATION

Refer to the applicable Material Safety Data Sheets and Technical Data Bulletins for applicable cautions and warnings.

A. Insulation Attachment

1. Versico DASH or FAST Adhesive may be specified for insulation securement as outlined in the Versico Technical Manual.
2. Versico Fasteners may be used, when specified, to secure Versico Insulation at the specified density outlined in the Versico Technical Manual.

B. Membrane Placement, Attachment and Hot Air Welding

1. A minimum of one perimeter sheet shall be installed at edges of each roof level and 12', 10' or 8' wide membrane shall be installed in the field of the roof.
2. Membrane sheets shall be mechanically fastened with the appropriate Versico Fastener/Fastening Plate spaced 6" to 12" on center, depending on project criteria, within the membrane splice. Refer to the Thermoplastic Specification for required number of perimeter membrane sheets and fastener spacing.
3. Overlap adjacent membrane sheets approximately 5-1/2" at those locations where Fastening Plates are located (along length of the membrane) and a minimum of 2" at end roll sections (width of the membrane).
4. Hot air weld the membrane sheets a minimum of 1-1/2" with an Automatic Hot Air Welding Machine.
5. Membrane that has been exposed to the elements for approximately 7 days must be prepared with Weathered Membrane Cleaner. Wipe the surface where Weathered Membrane Cleaner has been applied with a clean, dry HP Splice Wipe or other white rag to remove cleaner residue prior to hot air welding.

C. Additional Membrane Securement

The membrane must be secured at the perimeter of each roof level, roof section, expansion joint, curb, skylight, interior wall, penthouse, etc., at any angle change which exceeds 2" in one horizontal foot and at all other penetrations in accordance with Versico's Details published with Versico's Specifications.

D. Membrane Flashing

1. Flash all walls and curbs with VersiWeld reinforced membrane. Non-Reinforced membrane shall be limited to inside and outside corners, field fabricated pipe seals, scuppers and Sealant Pockets where the use of pre-molded accessories are not practical.
2. On vertical surfaces, such as walls, curbs and pipes, Bonding Adhesive is not required when the flashing height is 12" or less and the membrane is terminated under a metal counterflashing (nailed). When a coping or termination bar is used for vertical terminations, Bonding Adhesive may be eliminated for flashing heights 18" or less.
3. Terminate the flashing in accordance with an appropriate Versico Details above anticipated slush line.
4. When using the Pressure-Sensitive Cover Strip to overlay metal edging flanges or fasteners/plates, Versico Weathered Membrane Cleaner is used to clean surfaces as needed. Apply Versico TPO Primer prior to applying Pressure-Sensitive Cover Strip.

Copyright 2012 Versico

Versico and VersiWeld are Trademarks of Versico

Versico
P. O. Box 1289, Carlisle, PA 17013
Phone: 800-992-7663
www.versico.com

Physical properties of VersiWeld Membrane can be referenced in Part II, "Products" of the Thermoplastic Specification.

Attach copies of the applicable Versico Details that pertain to the individual project to complete a bid package submittal.